# Heyer Avenue Sidewalk Improvement Project

from Redwood Road to Center Street




Public Meeting May 6, 2025

## Agenda

- Project Overview
- Existing Conditions
- Project Goal & Proposed Improvements
- Construction Schedule

## **Project Location**



# **Existing Conditions**



Gaps in sidewalk



### Unimproved areas



Ponding of water



### Curb return with no ramp

# **Existing Conditions**

Cars parking on pedestrian pathway







## **Existing Conditions**

- Gaps in sidewalks
- Cars are often parked on pedestrian pathway without vertical curbs
- Sidewalk in deteriorated conditions at some locations
- Unimproved areas with lack of proper design
- Pedestrians walk in the shoulder or roadways
- Ponding of water due to lack of continuous standard curb and gutter

# **Project Goal**

To provide a safe and functional corridor for all users that:

- Enhances walkability and accessibility to local schools, businesses, and residences
- Implements pedestrian and bicycle facilities
- Improves traffic safety
- Improves drainage
- Treats roadway stormwater runoff
- Rehabilitates / repairs the pavement
- Improves corridor aesthetics





## Proposed Improvements

Continuous curb, gutter, & sidewalk



Intersection bulb-outs

ADA compliant curb ramps



High visibility crosswalks





## Proposed Improvements



**Bikeway facilities** 



Storm drain improvements



Pavement rehabilitation



#### Street light improvements

## Proposed Improvements



#### **Green Infrastructure Elements**





Street trees

## **Proposed Typical Section**

### (Redwood Rd to Madison Ave)




- Sidewalk (8 ft. wide)
- ☑ On-street parking
- ✓ Class II Bike Lane (both sides)
- ☑ Bulb-outs
- ☑ Street trees


## **Proposed Typical Section**

### (Madison Ave to Center St)




- Sidewalk (7 ft. wide)
- ☑ On-street parking
- ☑ Class II Bike Lane (both sides)
- ☑ Street trees














MATCHLINE











## **Utility Relocations**











## **Right-of-way**

- County ROW: 60 ft
- It is planned to construct within county ROW.
- Encroachments will be removed and property owners will be notified individually.

## **Project Schedule**

- Final Design: Summer/Fall 2025
- Advertise for bids: Fall 2025
- Utility relocation: Fall/Winter 2025
- Construction: Fall/Winter 2025

\* All dates are tentative.

### How to Reach Us:

Call: (510) 670-5480 email: <u>info@acpwa.org</u>

Website: www.acpwa.org